

ALL ELLE CUDA

### Detection Performance of Normalizer for a Multi-Pulse Signal Subject to Partially-Correlated Fading with Chi-Squared Statistics

A Paper Presented at the 2nd Joint Meeting of the Acoustical Societies of America and Japan, 15 November 1988, Honolulu, Oahu

Albert H. Nuttall Surface ASW Directorate





Naval Underwater Systems Center Newport, Rhode Island / New London, Connecticut

Approved for public release; distribution is unlimited.

### Preface

This research was conducted under NUSC Project No. A75205, Subproject No. RR00N01, "Applications of Statistical Communication Theory to Acoustic Signal Processing," Principal Investigator Dr. Albert H. Nuttall (Code 304). This technical report was prepared with funds provided by the NUSC In-House Independent Research and Independent Exploratory Development Program, sponsored by the Chief of Naval Research.

Reviewed and Approved: 8 December 1988

WAVM Workh

Associate Technical Director for Technology

UNC	LAS	SI	FI	ED			
CURITY	CLAS	SIF	ČΑ	ION	OF	THIS	DALLE

10 1 201/200

SECURITY CLASSIFICATION OF THIS PAGE			تنسنوا	24 00	19678		
	REPORT DOCU	MENTATION	PAGE				
1a. REPORT SECURITY CLASSIFICATION	16. RESTRICTIVE	1b. RESTRICTIVE MARKINGS					
UNCLASSIFIED							
2a. SECURITY CLASSIFICATION AUTHORITY	3. DISTRIBUTION/AVAILABILITY OF REPORT						
26. DECLASSIFICATION / DOWNGRADING SCHED	Approved for public release; distribution is unlimited.						
4. PERFORMING ORGANIZATION REPORT NUMBER	ER(S)	5. MONITORING ORGANIZATION REPORT NUMBER(S)					
TD 8453							
6a. NAME OF PERFORMING ORGANIZATION Naval Underwater	6b. OFFICE SYMBOL (If applicable)	7a. NAME OF MONITORING ORGANIZATION					
Systems Center	Code 304						
6c. ADDRESS (City, State, and ZIP Code)	3000 301	7b. AOORESS (City, State, and ZIP Code)					
i e		175. 255.65	·,,	LIF COOK)			
New London Laboratory							
New London, CT 06320		1					
8a. NAME OF FUNDING/SPONSORING ORGANIZATION	8b. OFFICE SYMBOL (If applicable)	9. PROCUREMENT INSTRUMENT IDENTIFICATION NUMBER					
Chief of Naval Research				_			
8c. ADDRESS (City, State, and ZIP Code)		10. SOURCE OF	FUNDING NUM	DERS			
Department of the Navy		PROGRAM ELEMENT NO.	PROJECT NO.	TASK	WORK UNIT		
Washington, DC 20362		ELEMENT NO.	1.00.	NO.	ACCESSION NO.		
11. TITLE (Include Security Classification)	<del></del>	1	<u> </u>				
	RMATITZER FOR A M	י שט חום_די וווו	STOWAT CITE	TECT TO D			
DETECTION PERFORMANCE OF NORMALIZER FOR A MULTI-PULSE SIGNAL SUBJECT TO PARTIALLY- CORRELATED FADING WITH CHI-SQUARED STATISTICS							
12. PERSONAL AUTHOR(S)	7441144			<del></del>			
Albert H. Nuttall							
13a. TYPE OF REPORT 13b. TIME C	OVERED	14. DATE OF REPO	RT (Year, Mone	th, Day) 15. PA	AGE COUNT		
16. SUPPLEMENTARY NOTATION		2,500 De	CEMPEL 0				
**			<b>K</b>				
17 COSATI CODES	18. SUBJECT TERMS (	ontinue on revers	e if necessary a	and identify by	block number)		
FIELD GROUP SUB-GROUP	Detection Pr	obability Correlated Fading Constant					
	Normalizer	Chi-Squared Fading False Alarm					
	Multi-Pulse	Signal t	Jnknown No	ise Level	Rate		
19. ABSTRACT (Continue on reverse if necessary	and identify by block n	umber)		V			
· ·					-		
ine raise alarm and	The false alarm and detection probabilities for a multipulse signal						
subject to partially correlated fading, in the presence of Gaussian noise of							
unknown level, are derived in closed form. The number & of signal pulses,							
as well as the number & of noise-only pulses used to estimate the noise							
background power level, are arbitrary. The power fading is characterized by							
a chi-squared distribution with 2m degrees of freedom and a normalized set							
of covariance coefficients $\{\rho_{K1}\}$ , all of which can be selected arbitrarily,							
in order to match an experimental realization or an actual measured							
situation. The performance capability of this processor depends additionally							
on the received signal-to-noise ratio. This study covers the case of a nonconstant threshold; comparisons of this normalizer with earlier results							
(for \$ = ∞) enable a quantitative evaluation of the losses incurred by							
WUNCLASSIFIED/UNLIMITED SAME AS I	18T (	21. ABSTRACT SECURITY CLASSIFICATION					
Albert H. Nuttall (203) 440-4618 Code 304							
DD FORM 1473, 84 MAR 83 APR edition may be used until exhausted. SECURITY CLASSIFICATION OF THIS AGE:							
<b>*</b>			2ECUR! I	T CLASSIFICATIO	IN UP THIS PAGES "NO		

83 APR edition may be used until exhausted. All other editions are obsolete. 10=11

SECURITY CLASSIFICATION OF THIS

19. ABSTRACT (Cont'd.)

 lack of knowledge of the noise level. The important capability of constant false alarm rate is achieved by this normalizer.

2 (4)

UNCLASSIFIED


SECURITY CLASSIFICATION OF THIS PAGE



### DETECTION PERFORMANCE OF NORMALIZER FOR A MULTI-PULSE SIGNAL SUBJECT TO PARTIALLY-CORRELATED FADING WITH CHI-SQUARED STATISTICS

BY

### ALBERT H. NUTTALL NAVAL UNDERWATER SYSTEMS CENTER NEW LONDON, CT 06320 USA



The following 5 pages give the text of the oral presentation at the JASA meeting.

The succeeding 8 pages constitute the poster presentation. The particular 5 pages that were employed for the oral presentation are labeled with VG1, VG2, VG3, VG4, VG5, at the top center.

The underwater propagation of acoustic signals is very adversely affected by the presence of deep fades in time and/or frequency. In an effort to combat fading, diversity in the transmitted signal is often employed, by emitting energy distributed over time and frequency. However, the fading of nearby pulses can be highly dependent, thereby thwarting some of the gains to be expected from diversity combination. This paper outlines the evaluation of the performance of a diversity-combining system in the presence of partially-correlated fading and additive noise of unknown level, in terms of the false alarm and detection probabilities.

The transmitted signal consists of K CW tone bursts, each of duration  $T_1$  seconds, distributed in a known pattern over time and frequency. The k-th received signal pulse undergoes an amplitude-scaling  $r_k$  and a phase-shift  $\theta_k$ , both of which are constant over an individual pulse duration of  $T_1$  seconds and bandwidth  $1/T_1$  Hertz. That is, we are considering slow non-selective fading.

The additive noise is stationary over the total observation time and has a flat spectrum over the total bandwidth utilized. However, since the noise level is unknown, a group of L noise-only bins, located in time-frequency where there is no signal, is used to extract an estimate of the noise level, N<sub>o</sub>.

In order to be quantitative about the fading statistics and dependencies, we define the power-scaling variate  $q_k = r_k^2$ , the square of the amplitude-scaling variate. The first-order probability density of q is taken to be chi-squared with 2m degrees of freedom. Thus m=1 corresponds to exponential power-fading or Rayleigh amplitude-fading. The parameter  $\hat{a}$  is a measure of the average strength of the fading. In particular, the average power scaling equals m times a. Particularly deep fading is modeled by small values of parameter m, which need not be integer. In fact, some recent measurements yielded fading which Was characterized by m near 1/2.

The statistical dependencies between fading of separate signal pulses is modeled by allowing arbitrary covariance coefficients between any two power scaling variates. The exact statistics and dependencies of phase shifts  $\theta_k$  are not relevant, due to the particular form of receiver processing adopted.

The potential-signal channels are matched-filtered and square-law envelope-detected at the instants of peak signal output, if signal is present. The sum of these K squared envelopes is then compared with a similar sum of L envelope-squared outputs of filters which are known to operate in a region of noise-only. If the ratio  $\nu$  exceeds a threshold, a signal is declared present.

For signal absent, the value of output  $\nu$  on any trial is independent of the absolute unknown noise level,  $N_0$ . Hence, this processor has constant false alarm rate capability; that is, we can realize a specified false alarm probability without knowledge of noise level  $N_0$ .


The detailed analysis of performance of this system is too lengthy to be presented here. All we can do is to present a sample which illustrates the type of results that are currently available. This plot gives the receiver operating characteristics on normal probability paper, with input signal-to-noise ratio as a parameter. This particular case is for four signal pulses subject to Rayleigh amplitude fading with a covariance coefficient of 0.5, and utilizing 16 noise-only filters. Many additional examples and a general program are available in NUSC Technical Report 8133, from which this paper was drawn.

CORRELATED FADING WITH CHI-SQUARED STATISTICS DETECTION PERFORMANCE OF NORMALIZER FOR A MULTI-PULSE SIGNAL SUBJECT TO PARTIALLY NUSC TR 8133

NAVAL UNDERWATER SYSTEMS CENTER USA ALBERT H. NUTTALL 06320 NEW LONDON, CT

PRESENTED AT
ACOUSTICAL SOCIETY OF AMERICA CONFERENCE
SHERATON-WAIKIKI HOTEL
HONOLULU, HAWAII

15 NOVEMBER 1988



OF K-TH SIGNAL PULSE RECEIVED SIGNAL (IF PRESENT): AMPLITUDE SCALING R 1/1, HERTZ BANDWIDTH PHASE SHIFT OR

ADDITIVE NOISE:

FLAT SPECTRUM OVER TOTAL BANDWIDTH UTILIZED. STATIONARY OVER TOTAL OBSERVATION TIME. UNKNOWN LEVEL.

# SIGNAL FADING STATISTICS

12, 04: CONSTANT OVER EACH INDIVIDUAL PULSE DURATION T, (SLOW FADING). ARBITRARY DEPENDENCIES BETWEEN PULSES.

DEFINE  $q_k = r_k^2 = POWER$  SCALING OF k-TH RECEIVED SIGNAL PULSE.

FIRST-ORDER PDF OF 9 IS CHI-SQUARED WITH 2m DEGREES OF FREEDOM:

$$p_{\epsilon}(u) = \frac{u^{m-1} \exp(-u/a)}{\Gamma(m) a^{m}} \quad \text{for } u > 0$$

AVERAGE POWER SCALING Q = ma FOR ALL k. m = 1 CORRESPONDS TO RAYLEIGH AMPLITUDE-FADING OR EXPONENTIAL POWER-FADING. m NEED NOT BE AN INTEGER.

# STATISTICS (CONTINUED):


ARBITRARY CORRELATION COEFFICIENTS BETWEEN POWER SCALINGS:

$$a_{kj} = \frac{q_k q_j - q_k q_j}{q_j^2}$$

PHASE SHIFTS (0,) HAVE ARBITRARY STATISTICS AND DEPENDENCIES.

ADDITIVE NOISE SPECTRAL LEVEL, N. MATTS/HZ, IS UNKNOWN.

## RECEIVER PROCESSING



TIME AND FREQUENCY SYNCHRONIZATION PRESUMED. (DELAY AND DOPPLER COMPENSATED)

FILTERING CAN BE ACCOMPLISHED VIA FFTS.

DECISION VARIABLE  $v = \frac{\chi(K)}{\chi_o(L)} \ge \text{THRESHOLD.}$ 

## PROBLEM DEFINITION

RELEVANT PARAMETERS:

K = NUMBER OF SIGNAL PULSES

L = NUMBER OF NOISE PULSES

SIGNAL FADING PARAMETER (NON-INTEGER); 2m DEGREES OF FREEDOM || || |2

 $R_{bi}$  = POWER-FADING COVARIANCE COEFFICIENT  $\overline{E}_i$  = AVERAGE RECEIVED SIGNAL ENERGY PER PULSE

No = SINGLE-SIDED RECEIVED NOISE SPECTRAL LEVEL

WANT PROB(v > 1HRESHOLD | SIGNAL PRESENT). CAN THEN DETERMINE  $P_F$  AND  $P_b$ .

L =  $\infty$  CORRESPONDS TO KNOWN NOISE LEVEL.

FOR SIGNAL ABSENT, & IS INDEPENDENT OF ACTUAL (UNKNOWN) NOISE LEVEL No; CFAR PROCESSOR.

CAN ACHIEVE SPECIFIED P. WITHOUT KNOWLEDGE OF No.

### ANALYTIC APPROACH

HOLD (r, ) AND (0, ) FIXED.

THEN CONDITIONAL CHARACTERISTIC FUNCTION (CF) OF SUM X(K) DEPENDS ONLY ON

S = \frac{x}{r\_a} = \frac{x}{x} = \frac{x}{x


APPROXIMATE S BY A CHI-SQUARED VARIATE WITH EXACT SAME MEAN AND VARIANCE.

AVERAGE THE CONDITIONAL OF TO GET THE UNCOND. OF D(K).

FOURIER TRANSFORM TO GET PDF OF X(K).

SERIES OF TERMINATING GAUSSIAN-HYPERGEOMETRIC FUNCTIONS. COMPUTE PROB( &(K) > T \* 1/2(L) ) IN TERMS OF A FINITE

VG5 SAMPLE RESULT



Probability of False Alarm Figure 25. ROC for K=4, m=1,  $\rho$ =.5, L=16

### INIITAL DISTRIBUTION LIST

Addressee	No. of Copies
CNA	1
ATIC	1